

Australasian Standard Project

Room Data Sheets

Department	Standard Components	Room Tag: 2100
Room Name	CT Scanning - Control Room	Room Code: CTCR
Area	6.0 M2	
No of Rooms	1	
Subtotal of Area		
Hours of Operation	Available 24 Hours	
Occupancy	Up to 2 staff	
Also covers these Rooms		
Description/ Special Requirements	<p>Room adjacent to CT Scanning Room/s with direct visibility to the patient for remote control of equipment, and review and reporting of procedure images. The Control room may serve two procedure rooms.</p> <p>Acoustics: Acoustic privacy is required</p> <p>Additional Design Considerations:</p> <ul style="list-style-type: none"> - Radiation shielding as advised by Radiation Consultant - Cable ducts from CT Scanning and Computer room may be required 	
Amendment	14.03.05, - First Draft	

Room Fabric and outline specifications

ID	Fabric	Material	Finish	Specification	Selection	Remarks
5060	Ceiling	Acoustic	Prefinished	Drop-in tiles, 600x1200		
6030	Cornice	Aluminium	Powdercoat	24mm shadow angle		
8000	Door protection	Vinyl	Prefinished	Kickplate, 300mm high		
9004	Doors	Solid Core/ glass	Paint	Single leaf, observation panel		staff entry/ exit; 910mm clear opening
1000	Floor finish	Vinyl	Standard slip resistant	Seamless, coved		
7025	Observation	Lead glass	Clear	Internal window		to procedure room
2000	Skirting	Vinyl	Prefinished	Floor vinyl coved, 150 mmH		
3000	Wall finish	Paint	Acrylic, washable			

Fittings and Furniture (FF)

ID	Description	Category	Group	Qty	Selection
2100	Chair: ergonomic, office	Furniture/ Fitting	3	2	
3400	Coathook	Metalwork	1	2	
22615	Table: computer	Furniture/ Fitting	3	1	small
24400	Whiteboard	Furniture/ Fitting	1	1	1200 x 900 optional

Fixtures, Equipment and associated Services (FE)

ID	Description	Group	Qty	Ele	Data	CdW	HtW	WmW	Tap	Dns	Gas	Selection
11400	Computer: PC & monitor	3	1	yes	yes	___	___	___	___	___	___	
62150	IMG: console, control	1	1	yes	yes	___	___	___	___	___	___	CT Scanning equipment
54510	Telephone: handset, standard	3	1	___	yes	___	___	___	___	___	___	

Australasian Standard Project
Room Data Sheets

Department | **Standard Components**
Room Name | **CT Scanning - Control Room**

Room Tag: 2100
Room Code: CTCR

Services

ID	Description	Service Category	Qty	Remarks
1040	Intercom	Communications	1	with handsfree microphone to CT Scan room
1006	Voice / Data outlet: double	Communications	3	1 outlet for telephone
5000	Airconditioning	HVAC		
6000	General fluorescent	Lighting		
9001	GPO: Double	Power	5	
9060	Special: for equipment	Power	1	CT Scanning equipment