Standard Components - Room Data Sheet

Room Name	Shower - Decontamination
Room Number:	SHDEC

Last modified	01/03/2016
Briefed Area	8.00
Remarks	
Occupancy	*1 - 2*
Hours of Operation	☑ *24 Hours*
Acoustics	
Description or Special Requirements	*The Decontamination Shower is provided to shower patients who arrive in the Unit contaminated with toxic and/or infectious substances. The room will include a flexible water hose, floor drain and contaminated water trap. The shower should be accessible from the ambulance bay without entering any other part of the Unit. A Personal Protective Equipment Bay may be located in close proximity.*

Room Fabrics

AusHFG code	Description	Material	Finish	Specification	Comments
1025	Floor finish	Vinyl, non slip	Studded	Seamless, coved	tiles also acceptable
3070	Wall finish	Vinyl	Prefinished	Wall vinyl full height	to wet areas; tiles also acceptable
5023	Ceiling - Plasterboard	Plasterboard	Prefinished	Water resistant, drop in tiles, 600x1200	
8010	Door protection	Composite	Prefinished PVC	Protection plate to 900 AFFL	Equal to Acrovyn
8040	Door protection	Composite	Prefinished PVC	To door frame	Equal to Acrovyn
9001	Door - 1100mm	Solid Core	Paint	Single leaf	910mm clear; Outward opening; privacy latch; emergency release.
6030	Cornice	Aluminium	Powdercoat	24mm shadow angle	
2000	Skirting	Vinyl	Prefinished	Floor vinyl coved, 150 mmH	or tiles for tiled floor

Fittings and Furniture

AusHFG code	Description	Group	Qty	Comments
FF-6152	Dispenser - disposable glove	2	2	

Fixtures, Equipment and associated Services

AusHFG code	Description	Grp	Qty	Ele	Data	CdW	HtW	WmW	Tap	Dns	Gas	Comments
FE-47605	Shower - decontamination	1	1	☐	☐	☑	☐	☑	☑	☑	☐	in lockable cabinet

Service Requirements

AusHFG code	Description	Comments
S-5015	Ventilation	
S-5019	Exhaust	to rangehood
S-6001	General: colour corrected	

Services

AusHFG code	Description	Group	Qty	Comments
S-4030	Drainage	1	1	to contaminated water trap
S-5015	Ventilation	1	1	

Room Name	Shower - Decontamination	Room Number: SHDEC

AusHFG code	Description	Group	Qty	Comments
S-5019	Exhaust	1	1	to rangehood
S-6001	General: colour corrected	1	1	
S-6200	Light switches	1	2	
S-8080	Emergency call	1	1	+ indicator button & light
S-7000	Oxygen (O2)	1	1	
S-7020	Medical Air (MA)	1	1	
S-7040	Suction	1	1	
S-11000	Wall panel	2	1	patient services panels