

Australasian Standard Project

Room Data Sheets

Department	Standard Components	Room Tag: 3870
Room Name	Set-up Room, 8m2	Room Code: SETUP-8
Area	8.0 M2	
No of Rooms	1	
Subtotal of Area	8.0 M2	
Hours of Operation	24 Hours	
Occupancy	1 - 2 intermittently	
Also covers these Rooms		
Description/ Special Requirements	A room for storage and holding of sterile stock for use in the Operating Unit, and set-up of case trolleys for operating procedures. The Set-up area will be located with direct access to Operating Rooms and ready access from CSSU for receipt of sterile stock.	
Amendment	15.05.05, - First Draft	

Room Fabric and outline specifications

ID	Fabric	Material	Finish	Specification	Selection	Remarks
5020	Ceiling	Plasterboard	Paint, scrub resistant	Flush set, suspended		
6030	Cornice	Aluminium	Powdercoat	24mm shadow angle		
8010	Door protection	Composite	Prefinished PVC	Protection plate to 900 AFFL		
8040	Door protection	Composite	Prefinished PVC	To door frame		
9004	Doors	Solid Core/ glass	Paint	Single leaf, observation panel		1050mm clear opening, sliding panel on doors to ORs
1000	Floor finish	Vinyl	Standard slip resistant	Seamless, coved		
2000	Skirting	Vinyl	Prefinished	Floor vinyl coved, 150 mmH		
3000	Wall finish	Paint	Acrylic, washable			
4020	Wall protection	Composite	Prefinished PVC	Crash rail at 900 AFFL		Equal to Acrovyn
4030	Wall protection	Composite	Prefinished PVC	Corner guards to 900 AFFL		Equal to Acrovyn, as required
7001	Windows					desirable

Fittings and Furniture (FF)

ID	Description	Category	Group	Qty	Selection
1252	Blind: Venetian integral	Furniture/ Fitting	1	1	to windows, if provided
2100	Chair: ergonomic, office	Furniture/ Fitting	3	1	to bench
3350	Clock: battery operated	Furniture/ Fitting	1	1	
5900	Desk	Furniture/ Fitting	3	1	
17255	Pedestal filing unit: mobile, 660mmH	Furniture/ Fitting	3	1	under desk
20000	Shelving unit: adjustable	Furniture/ Fitting	1	1	over desk, optional
10200	Trolley: instrument	Furniture/ Fitting	3	1	
24400	Whiteboard	Furniture/ Fitting	1	1	900 x 900, optional

Australasian Standard Project
Room Data Sheets

Department Standard Components
Room Name Set-up Room, 8m2

Room Tag: 3870
Room Code: SETUP-8

Fixtures, Equipment and associated Services (FE)

ID	Description	Group	Qty	Ele	Data	CdW	HtW	WmW	Tap	Dns	Gas	Selection
11400	Computer: PC & monitor	3	1	yes	yes	—	—	—	—	—	—	
54510	Telephone: handset, standard	3	1	—	yes	—	—	—	—	—	—	to desk

Services

ID	Description	Service Category	Qty	Remarks
1006	Voice / Data outlet: double	Communications	1	1 outlet for telephone
5005	Air conditioning: special	HVAC		HEPA filtered
5040	Pressure: positive	HVAC		
6000	General fluorescent	Lighting		
9001	GPO: Double	Power	2	