

Room Name	Audiology Testing Room		Room Number AUD-TR
Revision	4		
Issue Date	26.04.2021		
BRIEFING			
Briefed Area	14.00 m ²		
Hours of Operation	8am to 6pm, daily		
Occupancy	1 patient, 1 visitor/carer, 1-2 staff		
Acoustics	Acoustic isolation is required		
Remarks			
Description / Special Requirements	<p>The Audiology Testing Room provides an acoustically treated, soundproof space for clinical assessments to be carried out under controlled conditions. Testing Rooms may be modular proprietary items or constructed in situ and are generally designed as rooms within rooms in order to isolate the Testing Room from the rest of the building as much as possible. All designs should be reviewed and confirmed by an acoustic design expert.</p> <p>Additional Consideration:</p> <ul style="list-style-type: none"> The Audiology Testing Room currently indicates a layout (with an adjacent control room) that is suitable for paediatric testing. Layouts will vary to suit service requirements and the provided layout will need to be altered to suit services for older children and adults. The audiometric booth is to be ventilated and connected to air-conditioning, power and data. Noise from mechanical services is to be minimised with air-conditioning to be designed for low noise operation to meet ambient noise requirements for testing. The floor of the Treatment Room should be flush with the floor of the Control Room, or the adjacent corridor where a Control Room is not provided, for access by patients in wheelchairs. 		
SERVICES			
Electrical	BODY PROTECTED	<input checked="" type="checkbox"/>	CARDIAC PROTECTED <input type="checkbox"/>
HVAC	AIRCONDITIONING	<input checked="" type="checkbox"/>	AIRCONDITIONING: hepa filtered <input type="checkbox"/>
	AIRCONDITIONING: positive pressure	<input type="checkbox"/>	AIRCONDITIONING: negative pressure <input type="checkbox"/>
	EXHAUST: room exhaust	<input type="checkbox"/>	VENTILATION <input type="checkbox"/>
Lighting	LIGHTING: colour corrected	<input type="checkbox"/>	LIGHTING: dimmable <input type="checkbox"/>
	LIGHTING: downlights	<input type="checkbox"/>	LIGHTING: downlights, dimmable <input checked="" type="checkbox"/>
	LIGHTING: fluorescent/LED, downlights	<input type="checkbox"/>	LIGHTING: fluorescent/LED, flush with ceiling, tamper proof <input type="checkbox"/>
	LIGHTING: fluorescent/LED, general	<input type="checkbox"/>	LIGHTING: indirect <input type="checkbox"/>
Security / Nurse Call	NURSE CALL SYSTEM	<input type="checkbox"/>	

Room Fabrics

AusHFG code	Description	Comment
CLCN-009	CORNICE: wall trim fixing	
DWGL-005	DOOR: 910mm c/o, single leaf, observation panel, solid core/glass, paint	acoustic seals to suit testing requirements
DWPR-001	DOOR PROTECTION: kickplate, to 300 AFFL	
FLCP-006	FLOOR FINISH: carpet, carpet tiles, 90/10 wool/nylon	

Fittings, Furniture and Equipment (FF&E) Items

AusHFG code	Description	Group	Qty	Comment
MMAH-005	BOOTH: audiometric	3	1	with one way window (non-reflective)

Room Name | Audiology Testing Room
Room Number AUD-TR

AusHFG code	Description	Group	Qty	Comment
FIJO-212	BULKHEAD: joinery	1	1	plasterboard bulkhead also acceptable
FQBS-012	CHAIR: child	3	1	
FQBS-014	CHAIR: client	3	2	
FQBS-018	CHAIR: office, ergonomic	3	1	
ITNE-007	COMPUTER: desktop, with display screen	3	1	
MMAH-036	CONSOLE: control, audiometric booth	3	1	
FIJO-145	CUPBOARD: wall mount, double door, adj shelves, lockable	1	1	
FQDW-001	DESK: adj height, 1500W x 750D x 750H nom.	3	1	
MMAH-043	DEVICE: visual reinforcement audiometry	3	2	wall mounted, may be provided as a screen or puppet box, inclusion is dependent on service requirements
FIHR-029	HOOK: equipment	1	2	for headphones
FQBS-039	LOUNGE: 1 seat	3	1	
ITAV-061	SPEAKER: audiology	1	2	wall mounted, calibrated for testing space
FQTA-003	TABLE: children's play	3	1	

Engineering Services

AusHFG code	Description	Group	Qty	Comment
ITSE-006	BUTTON: duress, fixed	1	1	
ELGP-208	GPO: double, wall mounted	1	6	provision of emergency power to be determined based on service requirements
ITIN-026	OUTLET: data, double RJ45, wall mounted	1	1	
ELPR-006	RCD: residual current device	1	1	
MMSP-032	SERVICES PANEL: instrument jack	1	4	optional, as required for remote operation of equipment
ELBO-012	SWITCH: light, dimmer	1	1	