

Room Name	CT Scanning - Control Room		Room Number CTCR
<b>Revision</b>	3		
<b>Issue Date</b>	20.03.17		
<b>BRIEFING</b>			
<b>Briefed Area</b>	6.00 m <sup>2</sup>		
<b>Hours of Operation</b>	Available 24 Hours		
<b>Occupancy</b>	Up to 2 staff		
<b>Acoustics</b>	Acoustic privacy is required		
<b>Remarks</b>			
<b>Description / Special Requirements</b>	Room adjacent to CT Scanning Room/s with direct visibility to the patient for remote control of equipment, and review and reporting of procedure images. The Control room may serve two procedure rooms. Additional Design Considerations: Radiation shielding as advised by Radiation Consultant. Cable ducts from CT Scanning and Computer room may be required.		
<b>SERVICES</b>			
<b>General Requirements</b>	BODY PROTECTED = No	CARDIAC PROTECTED = No	
<b>Air</b>	AIRCONDITIONING = Yes	AIRCONDITIONING: hepa filtered = No	
	AIRCONDITIONING: positive pressure = No	AIRCONDITIONING: negative pressure = No	
	EXHAUST: room exhaust = No	VENTILATION = No	
<b>Lighting</b>	LIGHTING: colour corrected = No	LIGHTING: dimmable = No	
	LIGHTING: downlights = No	LIGHTING: downlights, dimmable = No	
	LIGHTING: fluorescent, downlights = No	LIGHTING: fluorescent, flush with ceiling, tamper proof = No	
	LIGHTING: fluorescent, general = Yes	LIGHTING: indirect = No	
<b>Nurse Call</b>	NURSE CALL SYSTEM = No		

**Room Fabrics**

AusHFG code	Description	Comment
CLTI-002	CEILING: acoustic, drop-in tiles, 600 x 1200	
CLCN-002	CORNICE: aluminium, 24mm shadow angle, powdercoat	
DWGL-005	DOOR: 910mm c/o, single leaf, observation panel, solid core/glass, paint	staff entry/ exit
DWPR-003	DOOR PROTECTION: kickplate, to 300 AFFL, vinyl, prefinished	
FLVY-007	FLOOR FINISH: vinyl, seamless, coved, standard slip resistant	
DWOB-009	OBSERVATION: internal window, lead glass, clear	to procedure room
FLSK-010	SKIRTING: vinyl, floor vinyl coved, 150H, prefinished	
WLWA-004	WALL FINISH: paint, acrylic, washable	

**Fittings, Furniture and Equipment (FF&E) Items**

AusHFG code	Description	Group	Qty	Comment
FQBS-018	CHAIR: office, ergonomic	3	2	
ITNE-007	COMPUTER: desktop, with display screen	3	1	
MMOP-014	CONTROL DESK: imaging	1	1	
MMMI-097	CONTROL UNIT: c/w display, control box and keyboard, CT	1	1	console for CT scanning equipment
FQDW-003	DESK: adj height, 800W x 900D x 750H nom., with shelf	3	1	small

**Room Name** | CT Scanning - Control Room

**Room Number** CTCR

AusHFG code	Description	Group	Qty	Comment
FIHR-026	HOOK: coat	1	2	
ITNE-049	TELEPHONE: handset, desktop	3	1	
FIBM-019	WHITEBOARD: fixed, magnetic	2	1	1200 x 900 optional

**Engineering Services**

AusHFG code	Description	Group	Qty	Comment
ELGP-208	GPO: double, wall mounted	1	6	
ELGP-106	GPO: single, special, for equipment	1	1	CT Scanning equipment
ITSE-029	INTERCOM: audio, wall mount	1	1	with handsfree microphone to CT Scan room
ITIN-026	OUTLET: data, double RJ45, wall mounted	1	3	1 outlet for telephone
ELBO-015	SWITCH: light, single	1	1	